BRUHAT BANGALORE MAHANAGARA PALIKE

BBMP/2020-21/OW/WORK_INDENT41623

APPROVED SCHEDULE - B

No.EE/BTP/BBMP/E-PMT/01/2020-21, Date: 05.05.2020

Name of Work:Providing water supply pipelines to various layouts of ward no. 8

Sl. No.	Approved Qty.	Description	Unit	Approved Tender Rates of SRIKANTH K S (AAKAR CONSTRUCTION)	
				In Figures	In Words
1	39.6	Cutting of road surface for pipeline trenches and disposing of the excavated stuff as directed including barricading, danger lighting etc., in the Asphalt road (Page No. 269, I. 37.38, PWDSR 2018-19)	Cum	410.0	Rupees Four Hundred Ten Only
2	296.99	Earthwork excavation for pipeline trenches including deporiting or bank up to a lead of 50 mtrs including shiriry and statting danger lighting and using site rails and boming poles at every 100 mtrs wherever necessary as directed in th following strructure manhole. (Page No. 6, I. 2.3, PWDSR 2018-19)	Cum	275.0	Rupees Two Hundred Seventy Five Only
3	39.6	Providing and filling sand in foundation upto plinth to required depth for sub soil treatment including watering ramming with all lead and lift complete as per specifications.(PWDSR 2018-19, P. 7, I.2.13)	Cum	1700.0	Rupees One Thousand Seven Hundred Only
4	440	Providing and fixing Chorinated Poly Venyl Chloride (CPVC) pipes conforming to IS 15778 having thermal stability for hot and cold water supply including all CPVC plain and brass threaded fittings, this includes jointing of pipes and fittings with one step solvent cement, trenching, refilling & testing of joints complete. (external work). - 50mm nominal OD pipes (PWDSR 2018-19, P. 99, I.13.87.6)	Rmtr	375.0	Rupees Three Hundred Seventy Five Only
5	257.39	Refilling the basement and pipeline treanches with secleted available earthe for trench excavation including authority condition in layers from thedi including disponsary of the sunplus earth with a heavy 200 m (Page No. 7, I. 2.11, PWDSR 2018-19)	Cum	105.0	Rupees One Hundred Five Only
6	4	KSRB 13.6.3-6 : Providing and fixing in position brass gate valve with C.I wheel of approved quality (screwed end) 50mm nominal bore including cost of all materials, labour and HOM of equipments with all leads complete as per specifications. (P. 94, I. 13.37, PWDSR 2018-19)	Each	1500.0	Rupees One Thousand Five Hundred Only
7	39.6	Providing, laying, spreading and compacting graded stone aggregate to wet mix macadam specification including premixing the Material with water at OMC in mechanical mix plant carriage of mixed Material by tipper to site, laying in uniform layers with paver in sub-base / base course on well prepared surface and compacting with vibratory roller to achieve the desired density complete as per specifications (Page No. 155, Item No. 20.18, PWD SR 2018-19)	Cum	1700.0	Rupees One Thousand Seven Hundred Only
8	264	KSRRB 500-1.1 : Cleaning the existing WBM road surface including removing of binding materials and other foreign matter with wire bushes and small picks, sweeping with brooms or soft brushes and finally dusting with old gunny bags and / or compressed air to receive bituminous treatment including cost of all materials, labour, HOM of machineries, curing complete as per specifications. Specification No.	Sqm	20.0	Rupees Twenty Only
9	264	KSRRB M500-6: Providing and applying primer coat for surfaces of medium porosity like cement stabilized soil base @ 1.10 Kg/Sqmt over prepared surface with S.S bitumen emulsion using bitumen tanker fitted with spray set (excluding cleaning of road surface) including cost of all material, labour HOM of machineries complete as per specifications.	Sqm	40.0	Rupees Forty Only
10	10.56	KSRRB M500-18: Providing and laying semi dense bituminous concrete using crushed aggregates of specified grading, premixed with bituminous binder and filler, transporting the hot mix to work site, laying with a paver finisher to the required grade, level and alignment, rolling with smooth wheeled, vibratory and tandem roller to achieve the desired compaction as per MORTH specifications clause No. 508 complete in all respects as per specifications. using 40-60 TPH capacity HMP with mechanical paver grading I (35-40mm) with 4.5% VG-30 Bitumen (Page No. 160, Item No. 21.20.5, PWD SR 2018-19)	Cum	6500.0	Rupees Six Thousand Five Hundred Only

Signature of the Contractor

Executive Engineer
Byarayanapura Division
BBMP, Bangalore - 92
15/06